BRUHATH BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE ELECTRICAL DIVISION

Office of the Executive Engineer
Electrical Division, Yelahanka Zone.
Bruhath Bengaluru Mahanagara Palike

"Schedule B"

Name of the work :-Maintenance of Aerators and related Lightings in Yelahanka old town and Allalsandra lake in ward no 1&4 and Repairs of Electrical Installations to BBMP buildings coming under yelahanka Division

Sl.No	Qty	Description Of Work	Unit	Quoted Rates	
				In figures	In words
1	190	Licenced electricial wiremen with tools (Skilled) Rs.605.56/Person/Day. KAE31LMW 2017 Dated 30-12-2017 Minium Wages and VDA From 01-04-2021 to 31-03-2022	Days	605.56	Rupees Six Hundred Five And Paise Fifty Six Only
2	190	Assistant electricial wiremen (semiSkilled) Rs.556.53/Person/Day. KAE31LMW 2017 Dated 30-12-2017 Minium Wages and VDA From 01-04-2021 to 31-03-2022	Days	556.53	Rupees Five Hundred Fifty Six And Paise Fifty Three Only
3	200	Helper (Assistent) Rs.511.95/Person/Day. KAE31LMW 2017 Dated 30-12-2017 Minium Wages and VDA From 01-04-2021 to 31-03-2022	Days	511.97	Rupees Five Hundred Eleven And Paise Ninety Seven Only
4	4	Plastic Mug	Nos	10.00	Rupees Ten Only
5	4	Plastic buckets 20 L capacity	Nos	40.00	Rupees Forty Only
6	10	Coir Brush	Nos	20.00	Rupees Twenty Only
7	94	Wiring for lighting/power circuit using one of **FRLS** PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments.1.5 sqmm	Mtrs	2.00	Rupees Two Only
8	200	Wiring for lighting/power circuit using one of **FRLS** PVC insulated 1100V grade. multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments.4 sqmm	Mtrs	5.00	Rupees Five Only
9	1	Supplying of Switch disconnector fuse unit (TPN) HRC type (but without HRC fuses). With AC-23A duty and as per IS-13947.160Amps	Each	4000.00	Rupees Four Thousand Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
(ವಿದ್ಯುತ್) ಯಲಹಂಕ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

10	11	Supplying and fixing HRC fuse link on existing switch fuse base with watt loss as per IS-13703.Up to 63Amps	Each	100.00	Rupees One Hundred Only
11	9	Supplying and fixing HRC fuse link on existing switch fuse base with watt loss as per IS-13703.Above 63 Amps to 200 Amps	Each	100.00	Rupees One Hundred Only
12	5	Supply and fixing of 4pole power contactor with NO/NC contacts on existing wood/panel board using necessary bolts, nuts, washers and wiring etc., complete with AC-3 Rating and as per IS-13947.60 to 70Amps	Each	1500.00	Rupees One Thousand Five Hundred Only
13	2	Supply and fixing of 4pole power contactor with NO/NC contacts on existing wood/panel board using necessary bolts, nuts, washers and wiring etc., complete with AC-3 Rating and as per IS-13947.160	Each	6000.00	Rupees Six Thousand Only
14	6	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes95 Sq mm.	Each	100.00	Rupees One Hundred Only
15	4	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts, necessary phase separators, handle and wiring complete. Protection of Overload and Short circuit with thermal Magnetic/Micro processor release and Earth Fault as per IS-13947. (Icu = Ics)FOUR POLE 125 Amps 25kA.	Each	3500.00	Rupees Three Thousand Five Hundred Only
16	15	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.6-32Amps SP	Each	50.00	Rupees Fifty Only
17	5	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.6-32Amps DP	Each	60.00	Rupees Sixty Only
18	5	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.50-63Amps TPN	Each	500.00	Rupees Five Hundred Only
19	6	Supplying and fixing of LED type panel board indicating lamp with required colour suitable for 230/440v A.C. 50 Hz 12/24v D.C.	Each	5.00	Rupees Five Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
(ವಿದ್ಯುತ್) ಯಲಹಂಕ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

20	400	Supplying of 1.1 KV LT UG cable XLPE or Heat resistant PVC insulated, PVC extruded Inner sheath armoured UG LT cable as per IS-1554 (Part-1) or IS-7098 Part-1, Armouring strip thickness in average +5% and resistivity 14 Ohms/Kms (Max) as per IS-3975 3.5 core 25 sqmm	Mtrs	100.00	Rupees One Hundred Only
21	400	Supplying of 1.1 KV LT UG cable XLPE or Heat resistant PVC insulated, PVC extruded Inner sheath armoured UG LT cable as per IS-1554 (Part-1) or IS-7098 Part-1, Armouring strip thickness in average +5% and resistivity 14 Ohms/Kms (Max) as per IS-3975 3.5 core 70 sqmm	Mtrs	200.00	Rupees Two Hundred Only
22	350	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.25 sqmm to 75 sqmm On wall /Structure	Mtrs	2.00	Rupees Two Only
23	250	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100Volts **as per IS-694:1990.3C X 4.0Sq.mm**	Mtrs	5.00	Rupees Five Only

I am prepared to take up the above work at rates quoted in the Schedule 'B'

Contractor

EXECUTIVE ENGINEER
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
(ELEC)
(ವಿದ್ಯುತ್) ಯಲಹಂಕ
BBMP, Yelahanka Zone
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ